

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I.D. Morgan Operator Well No.: 7289

LOCATION: Elevation: 964' Quadrangle: Big Run W.Va
District: Grant County: Wetzel
Latitude: 39.50640 Feet South of 39 Deg. 30 Min. 23.04 Sec.
Longitude: -80.52204 Feet West of -80 Deg. 31 Min. 19.34 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources INC. Coal Operator West Virginia Land Resources INC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 5/23/23 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew A. Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 22th day of December, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thrustopic with Green Dye Gas Becker	1006'	574'		
Expandable Cement	574'	Surface		
8 5/8" Casing	678'	Unknown	0'	Unknown
16" Conductor	Surface	18'	0'	18'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 26th day of January, 2024.

And further deponents saith not. Matthew A. Yearlsey

Thomas Thrasher

Sworn and subscribe before me this 21st day of February, 2024



My commission expires: August 17, 2025 [Signature]
Notary Public

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ROBERT M. ROE
Lease or Property Owner
2532 Mannington Road, Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.Va
Well Location
GRANT
District
WETZEL
County
7289
Well No.
I.D. MORGAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING Stephen McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 22th day of December 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned hole with 12 1/4" bit from surface to 509'. Reduced to 9 7/8" bit and cleaned 9 7/8" hole from 509' to 678'. Tagged top of 8 5/8" casing at 678'. Reduced to 6 1/4" bit and cleaned 6 1/4" hole from 678' to 774'. Cleaned 6 1/4" hole through the Pittsburgh Coal Seam (774' - 780.5'). Cleaned 6 1/4" hole from 780.5' to 1006'. Cut 8 5/8" casing at 980.5' and 790.5'. A diligent effort was made to remove 8 5/8" casing by pulling 150% of the string weight. All attempts were unsuccessful. Perforated the 8 5/8" casing at 980.5', 930.5', 880.5', 830.5', 790.5' 785.5', 780.5', 779', 777.5', 776', 775', 774', 769', 764', 724' with 6 shots at each depth. Cemented hole from 1006' to surface as follows: Cemented bottom of hole from 1006' to 574' with 150 sacks of Thixotropic cement with a green dye and gas block additive. Cemented from 574' to surface with 410 sacks of expanding cement. Cement did circulate at the surface. A total of 560 sacks of cement were used to fill the hole from 1006' to surface. Left 18' of 16" conductor casing in the hole from 18' to surface.	8 5/8" Casing 16" Conductor Casing	0' 0'	Unknown 18'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>774' - 780.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 26th day of January, 2024

And further deponents saith not.


Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 20th day of February 2024

My commission expires

June 8, 2027



Christopher Willis
Notary Public

Permit No. 47-103-03584-00-00
Well No. 7289
Latitude: 39° 30' 23.04"N
Longitude: -80° 31' 19.34"W