

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: L. Stanton Leezer Operator Well No.: 8097B

LOCATION: Elevation: 1469' Quadrangle: Hundred W.VA, PA
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 53.88 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 43.29 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 06/29/2023 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 14th day of July, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1505'	1183'	8 5/8" Casing - 447'	Unknown - Multiple perforations placed in remaining casing
Thixotropic Cement	1183'	1092'	16" Conductor - 0'	20'
Expandable Cement	1092'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 3rd day of August, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 14th day of September, 2023

My commission expires: June 8, 2027
Notary Public
Stephen Mccoy
Digitally signed by Stephen Mccoy
Date: 2023.09.20 07:39:49 -04'00'



RECEIVED
Office of Oil and Gas
SEP 26 2023

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

WV Department of Environmental Protection
10/20/2023

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

LEEZER FAMILY TRUST (C/O KIMBERLY HIMES)
Lease or Property Owner
P.O. BOX 933 BARRACKVILLE, WV 26559
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED W.VA, PA
Well Location

CHURCH
District

WETZEL
County

8097B
Well No.

L. STANTON LEEZER
Farm

Digitally signed by Stephen Mccoy
Date: 2023.09.20 07:39:08 -04'00'

STATE INSPECTOR SUPERVISING PLUGGING Stephen Mccoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of July, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 12 1/4" hole from the surface to 260'. Cleaned a 9 7/8" hole from 260' to the top of the existing 8 5/8" casing at 814'. Cleaned a 7 7/8" hole from 814' to 1505'. Cut 8 5/8" casing at 1498.5'. Removed 447' of 8 5/8" casing from 814' to 1261'. The 8 5/8" casing separated at 1296 and became lodged in the hole at 1009'. A diligent effort was made to remove the 8 5/8" casing from 1009' to 1044' but all efforts were unsuccessful. Left 35' of 8 5/8" casing in the hole from 1009' to 1044'. Left an unknown amount of 8 5/8" casing in the hole from 1296' to an unknown depth. Perforated remaining 8 5/8" casing with 6 shots at each of the following depths: 1448.5', 1398.5', 1348.5', 1308.5', 1305.5' and 1298.5'. 8 5/8" casing was parted from 1324' to 1327.5'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1292.5 - 1298.5'). Left 20' of 16" conductor pipe in the hole from the surface to 20'. <u>Cemented the hole from 1505' to the surface as follows:</u> From 1505' to 1183' with 180 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 1183'. Cemented the hole from 1183' to the surface with 55 sacks of Thixotropic Cement and 535 sacks of Expandable Cement. Cement did circulate at the surface. A total of 770 sacks of cement were used to fill the hole from 1505' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1292.5' - 1298.5'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 3rd day of August, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 14th day of September, 2023

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03592
Well No. 8097B
Latitude: 39° 39' 53.88"N
Longitude: -80° 24' 43.29"W

RECEIVED
Office of Oil and Gas

SEP 26 2023

WV Department of
Environmental Protection