

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Lindsey Stewart Operator Well No.: 7425

LOCATION: Elevation: 1279' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 57.77 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 38.99 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 08/24/2023 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 23rd day of August, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1360'	847'	7" Casing - 77'	Unknown
Expandable Cement	847'	Surface	16" Conductor - 0'	20'


Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of September, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 25th day of September, 2023

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
SARAH J. GOODRICH ETAL
Lease or Property Owner
433 BUCK RUN RD. SMITHFIELD, WV 26437
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7425
Well No.
LINDSEY STEWART
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of August, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
<u>Formation</u>				
Cleaned a 12 1/4" hole from the surface to 278'. Cleaned a 9 7/8" hole from 278' to 1180'. Cleaned a 7 7/8" hole from 1180' to top of existing 7" casing at 1216'. Cleaned a 6 1/4" hole from 1216' to 1360'. Removed 77' of 7" casing from the 1216' to 1293. A diligent effort was made to remove existing 7" casing by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1293' to an unknown depth. Cleaned a 9 7/8" from 1216' to 1231'. Cleaned a 6 1/4" hole from 1231' to 1360. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1087' - 1093'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	7" Casing 16" Conductor	77' 0'	Unknown 20'	
<u>Cemented the hole from 1360' to the surface as follows:</u> From 1360' to 847' with 265 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 847'. Cemented the hole from 847' to the surface with 525 sacks of Expandable Cement. Cement did circulate at the surface. A total of 790 sacks of cement were used to fill the hole from 1360' to the surface.				
<u>Coal Seams</u>		<u>Description of Monument</u>		
<u>Pittsburgh</u>	1087' - 1093'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of September, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 25th day of September, 2023

Christopher Andrew Willis
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03604
Well No. 7425
Latitude: 39° 30' 57.77"N
Longitude: -80° 31' 38.99"W

