



REGULATED GAS CONVEYANCE - 1/28

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

December 30, 1923

WELL RECORD


Permit No. 998-A Well purchased from - Hops Natural Gas Co., Oil or Gas Well GAS
(KIND)

Company Equitable Gas Company - W. Va Div.
 Address Clarksburg, West Va.
 Farm Peter Solos Acres 95
 Location (waters) Mano. N/W. 1-3-4
 Well No. 5436 Elev. 1082' VA
 District Church County Netool
 The surface of tract is owned in fee by Mrs. Beaula Stewart
Garrison, Pa.,
 Address _____
 Mineral rights are owned by Lillie Stottlarire, et al.
Hundred, W. Va.
 Address _____
 Drilling commenced August 15, 1936
 Drilling completed October 4th, 1936
 Date Shot _____ From _____ To _____
 With _____
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water _____ feet _____ feet
 Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	315'	315'	Size of
8 1/4	1308'	768'	
6 5/8	2008'	2008'	Depth set
5 3/16	2650'	2650'	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT 808 FEET 72 INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Un-recorded			0	808			
Pgh. Coal			808	814			
Un-recorded			814	1326			
Big Dajun			1326	1375			
Un-recorded			1375	1590			
1st. Salt Sand			1590	1670			
Un-recorded			1670	1780			
2nd. Salt Sand			1780	1810			
Un-recorded			1810	1990			
Little Lime			1990	1965			
Un-recorded			1965	1990			
Big Lime			1990	2050			
Big Dajun			2050	2290	Gas	2050'	
Un-recorded			2290	2650			
30 Ft. Sand			2650	2685			
Un-recorded			2685	2811			
30 Ft. Sand			2811	2825			
Garden Stray			2825	2885	Gas	2878'	
Un-recorded			2885	2895			
Garden Sand			2895	2925			
Un-recorded			2925	2968			
4th. Sand			2968	2975			
Un-recorded			2975	3032			
5th. Sand			3032	3040	Gas	3038'	
Un-recorded			3040	3055			
Total Depth.....				3055			



(Over)

MAY 10 1954

Record of Well No. 5416 Located on Peter Sole et ux Farm August 19 06.
 Church District Wetzel County West State
 Division "I" District No. 11 Drilled under well Order
 Rig built by Began August 4th, 19 06 Completed August 10th, 19 06.
 Well drilled by Carnahan Drilling Co. Began August 15th, 19 06. Completed October 4th, 19 06.
 Depth of Well 3055 feet Size of Hole 5-3/16" Producing Gas

Elev: 1082G

Well purchased from the Hope Natural Gas Company, under agreement dated July 1st, 1939.

CASED WITH			REMARKS
AMOUNT	SIZE	KIND	
315 Ft.	10"		Pulled out 540 Ft.&.3", Left 767 Ft.&.9" of 8-1/4" Csg.
1308 Ft.	8-1/4"		
2008 Ft.	6-5/8"		
2650 Ft.	5-3/16"		
3059 Ft 10"	2"		

COAL VEINS

FORMATIONS

NAME	TOP	BOTTOM	OIL	GAS	WATER	REMARKS
Pittsburgh Coal	808	814				
Big Dunkard	1336	1375				
First Salt Sand	1590	1670				
Second Salt Sand	1780	1840				
Little Lime	1950	1965				
Big Lime	1992	2050				
Big Injun	2222	2220		2058		
Fifty Foot Sand	2258	2285				
Thirty Foot Sand	2311	2325				
Gordon Stray	2366	2385		2278		
Gordon Sand	2395	2395				
Fourth Sand	2368	2375				
Fifth Sand	3032	3040		3058		
Total Depth		3055				

1946
 Filled from 3055
 to 2900 Cement.

