



1571

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle Littleton
Permit No. 1100 A

WELL RECORD

Oil or Gas Well Gas
(KIND)

Company A. M. Snider
Address Hundred, W. Va.
Farm Aaron Bassett Acres 290
Location (waters) Bear Run
Well No. 572 Elev. 785'
District Green County Wetzel
The surface of tract is owned in fee by Mrs. Ida Bassett
P.O. Box 23 Address Reader, W. Va.
Mineral rights are owned by Mrs. Ida Bassett
P.O. Box 23 Address Reader, W. Va.
Drilling commenced May 2, 1904
Drilling completed July 28, 1904
Date Shot _____ From _____ To _____
With _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
WELL ACIDIZED _____
WELL FRACTURED _____


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer _____
13			<u>6x5 B.H.</u>
10	<u>485'</u>	<u>485'</u>	Size of _____
8 1/4	<u>964'</u>	<u>964'</u>	<u>5x2 C.A. set 2521</u>
6 5/8	<u>1750'</u>	<u>1750'</u>	<u>3x5 L.A.</u>
5 3/16	<u>1950'</u>	<u>1950'</u>	Depth set _____
3			<u>4x2 A. set 2426'</u>
2	<u>2749'</u>	<u>2749'</u>	Perf. top _____
Liners Used			Perf. bottom _____
			Perf. top _____
			Perf. bottom _____

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES
_____ FEET _____ INCHES FEET _____ INCHES

RESULT AFTER TREATMENT _____
ROCK PRESSURE AFTER TREATMENT _____
Fresh Water _____ Feet _____ Salt Water _____ Feet _____

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Pitts. Coal			462				
Dunkard sand			870	975			
Gas sand			985	1075			
Salt sand			1200	1550			
Maxon sand			1615	1650			
Injun sand			1730	1990	Gas	1742;1784;1842	
Stray sand			2545	2561	Water	1866	
Gordon sand			2563	2582	Gas	2545	
Total Depth			2584		Gas	2563	
Drilled deeper			2725				



(over)

APR 6 1962