

POCAHONTAS LAND COORDINATES

N 46,444.636
E -13,914.767

REFERENCES
N.T.S.

Gas Well 47-047-1116

Berwind Land Company - Coal, Oil and Gas
U.S. Steel Mining Company, LLC - Pocahontas No. 3 Seam Lessee
Berwind Group Oil and Gas Limited Partnership - Oil and Gas Lessee
CDX Gas, LLC - CBM Lessee

Notes:

No known domestic water supplies within 1000 feet.

(+) Denotes location of well on USGS map.

FILE No. CDXGAS
DRAWING NAME \PLAT\S-6B
Drawing Number 3-20-00-3SP
SCALE 1" = 1000'
MINIMUM DEGREE OF ACCURACY 1 : 2500
PROVEN SOURCE OF ELEVATION USGS B.M. F44 El. 1565

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DEPARTMENT OF MINES.

(SIGNED) W. Claude Banner Jr.
R.P.E. 2430 R.P.S. _____

W. CLAUDE BANNER, JR. REGISTERED 2430 STATE OF WEST VIRGINIA PROFESSIONAL ENGINEER

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
NITRO, WV

DATE **AUGUST 31, 2000**
OPERATOR'S WELL No. **S-6B(r)**
API WELL No. 47 - 109 - 01954C
STATE COUNTY PERMIT

WELL TYPE: OIL__ GAS **CBM** LIQUID INJECTION__ WASTE DISPOSAL__
(IF "GAS") PRODUCTION **X** STORAGE__ DEEP__ SHALLOW__ horizontal

LOCATION: ELEVATION **2147.94** WATER SHED **BAILEY BRANCH OF INDIAN CREEK**
DISTRICT **CENTER** COUNTY **WYOMING**
QUADRANGLE **WELCH, WV**

SURFACE OWNER **BERWIND LAND COMPANY** ACREAGE **867.22 Tax Map 143 - Parcel 1**
CBM ROYALTY OWNER **BERWIND LAND COMPANY** LEASE ACREAGE **2940.66**
LEASE No. _____

PROPOSED WORK: DRILL **X** CONVERT__ DRILL DEEPER__ REDRILL__ FRACTURE OR STIMULATE__ PLUG OFF OLD FORMATION__ PERFORATE NEW FORMATION __ OTHER PHYSICAL CHANGE IN WELL (SPECIFY)_____

PLUG AND ABANDON ___ CLEAN OUT AND REPLUG ___

TARGET FORMATION **POCAHONTAS NO. 3 & NO. 4 SEAMS** ESTIMATED DEPTH **1501'**
WELL OPERATOR **CDX GAS, LLC** MANAGER **JOSEPH ZUPANICK**
ADDRESS **P.O. BOX 609** ADDRESS **P.O. BOX 609**
PINEVILLE, WV 24874 **PINEVILLE, WV 24874**

OCT 06 2000

6-6 272

WYO 1954 C

WR-35

API # 47- 109-01954 C

State of West Virginia
Division of Environmental Protection
Section of Oil & Gas

Well Operator's Report of Well Work

Farm name: Berwind Land Company Operator Well No: S-6B(r)

Location: Elevation: 2,147.98 Quadrangle: WELCH

District: CENTER County: WYOMING

Latitude: 2300 Feet South of 37 Deg. 30 Min. 00 Sec.
Longitude: 4550 Feet West of 81 Deg. 35 Min. 00 Sec.

RECEIVED
Office of Oil & Gas
SEP 14 2001
WV Department of
Environmental Protection

Company: CDX Gas, LLC
P.O. Box 609
Pineville, WV 24874

Agent: JOSEPH A. ZUPANICK

Inspector: OFIE HELMICK
Permit Issued: 10/02/00
Well Work commenced: 01/17/01
Well Work completed: 06/18/01
Verbal plugging
Permission granted on:
Rotary x Cable _____ Rig
Total depth (ft) 1479'
Fresh water depths (ft) N/A
Salt water depths (ft) N/A
Is coal being mined in the area (Y/N)? Y
Coal depths (ft): 506, 611, 648, 653, 730, 881, 1027, 1284, 1367, 1424

Casing & Tubing Size	Used in Drilling	Left in Well	Cement Fill up
13 3/8"	30'	30'	Surface
9 5/8"	308'	308'	Surface
7"	1,137'	1,137'	Surface
2 7/8"	1,411'		Hanging

OPEN FLOW DATA

Producting formation Pocahontas No. 3 and No. 4 Seams Pay zone depth (ft)
Gas: Initial open flow N/A Mcf/d Oil: Initial open flow ____ Bbl/d
Final open flow N/A Mcf/d Final open flow ____ Bbl/d
Time of open flow between initial and final tests: _____ hours
Static rock pressure _____ psig (surface pressure) after _____ hours

Second Producing formation _____ Pay zone depth (ft)
Gas: Initial open flow N/A Mcf/d Oil: Initial open flow ____ Bbl/d
Final open flow N/A Mcf/d Final open flow ____ Bbl/d
Time of open flow between initial and final tests: _____ hours
Static rock pressure _____ psig (surface pressure) after _____ hours

Note: ON BACK OF THIS FORM, PUT THE FOLLOWING: 1) DETAILS OF PERFORATED INTERVALS, FRACTURING OR STIMULATING, PHYSICAL CHANGE, ETC. 2) THE WELL LOG WHICH IS A SYSTEMATICK DETAILED GEOLOGICAL RECORD OF ALL FORMATIONS, INCLUDING COAL ENCOUNTERED BY THE WELLBORE.

For: Joseph Zupanick
CDX Gas, LLC
By: J. A. Zupanick
Date: 9/10/01

SEP 14 2001

WYD 1954 C

Operator: S-6B(r)
API No. 47- 109-01954 C
Location: Wyoming County

Details of Perforated Intervals, Fracturing or Stimulation, Physical Change, Etc.

N/A

Well Log & Geologic Record - Depths from K.B.

Formation	Top	Bottom
Overburden	0	10
Shale	10	20
Sandyshale	20	241
Sandstone	241	350
Sandyshale	350	421
Sandstone	421	506
Coal	506	507
Sandyshale	507	514
Sandstone	514	611
Coal	611	613
Sandyshale	613	623
Sandstone	623	648
Coal	648	650
Shale	650	653
Coal	653	656
Sandyshale	656	730
Coal	730	731
Sandyshale	731	881
Coal	881	883
Sandystone	883	960
Sandyshale	960	1027
Coal	1027	1145
Snadyshale	1029	1191
Sandstone	1145	1275
Sandyshale	1191	1284
Shale	1275	1285
Coal	1284	1310
Shale	1285	1365
Sandyshale	1310	1367
Coal Poca #4	1367	1371
Sandyshale	1371	1424
Coal - Poca #3	1424	1429
Sandyshale	1429	1479